TUMKUR DIVISION.

Dated 23rd January 1928.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 20th February 1928, for constructing a Middle School building at Tiptur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M. on all days except Sundays and holidays.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer.

4. Each tender must be accompanied by a deposit of rupees 500 (five hundred only) in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for constructing Middle School building at Tiptur, in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The rate should be noted both in figures and in words in the special forms without any corrections or addition.

10. No claims for any higher rate on any account will be entertained after the tender is accepted.

11 By failure to show the stipulated progress monthly the tenderer will be liable for removal, fine and forfeiture of earnest money.

12. In matter of all dispute about rates, measurements, quality of work, etc., the decision of the Chief Engineer will be final and legally binding.

Approximate quantities of work.

Serial No.	Items of work	Per	Quantity	Rate	
				In figures	In words

Abstract of quantities required for the construction of Middle Schools building at Tiptur :—

No.	Items of work	Unit	Quantity
1	Earth excavation of foundation ordinary soil and filling in basement.	C.yd.	148
2	Burnt stone in clay foundation and basement	C.ft.	6,272
3	Burnt brick in clay superstructure	„	7,187
4	Burnt brick in chunam	„	745
5	Do arch work	„	208
6	Burnt stone slabs 6″ thick roughly dressed	Sqr.	1,016
7	Teakwood work wrought and put up with wood oiling ...	C.ft.	470·99
8	Roofing with first class Mangalore pattern Tumkur tiles on teek reepers, nails, etc., with eave tiles tied up by a teak wood batton screwed down to the rafters.	Sqr.	84·23
9	Ridge tiles set in mortar and cement pointed	R.ft.	312
10	Rough plastering with one coat ½″ thick well rubbed with trowel and pressed with pebbles from sand sereening thrown on the surface to get the effect of rough cast work.	Sqr.	184·56
11	White and colour washing two coats	„	191·56
12	Perforated brick work	No.	30
13	Tarring wood work	Lumpsum	

No.	Items of work	Unit	Quantity
14	Flooring with 9″ square 1st class Mangalore pattern Tumkur tiles on 3″ stone jelly concrete in chunam bed and pointed with cement.	Sqr.	37·67
15	Flooring with 1½″ thick Cudapah slab on 3″ stone jelly concrete in chunam bed and cement painting.	,,	8·86
16	Teak wood eave board ordinary with painting	R.ft.	674
17	Cement pointing to basement	Sqr.	1,090
18	Ornamental work such as string course with smooth plaster 4″ wide at top pillasters outside around windows and ventilators.	Lump sum	
19	Chunam borders	R.ft.	250
20	Clearing site and unforeseen works	Lump sum	
21	Cutting V.-Shape in stone pillars	Each	28
22	Teak wood finials at ends	,,	7
23	Teak wood doors (4′×7′) panelled shutters as per Marryot's specification complete with glazed ventilators on top.	S.ft.	140
24	Teak wood windows 3½′×5′ and 3′×5′ with panelled shutters, iron bars ¾″ dia. 4″ apart witr iron fittings as per Marryot's specifications complete.	,,	119
25	Teakwood glazed ventilators over windows	,,	36
26	Teakwood planks and zinc sheets for vallys with chunam and cement gutters.	,,	51
27	Silicate painting three coats	Sqr.	5·90
28	Inscription stone	Lump sum	
29	Plastering white chunam one coat rubbed with trowel complete to compound wall.	Sqr.	6·79
30	Wrought iron gate way including painting	S.ft.	64

Abstract Notification.

The attention of the public is invited to the notice calling for tenders for restoring Bhangihalli Tank in Gubbi Taluk, published in the *Mysore Gazette*, dated 19th January 1928, Part VI, pages 75 and 76.

V. V. PATANKAR,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

MYSORE HORTICULTURAL SOCIETY.

Notification dated 13th January 1928.

The Winter Horticultural Show will be held at Lal-Bagh on Saturday and Sunday the 4th and 5th February 1928. It will be open on Saturday at 3 P.M. for the members of the Horticultural Society and at 4 P.M. for the public. On Sunday it will be open from 8 A.M. to 8 P.M. The Horticultural Show ticket will admit the public to the Poultry Show also which will be held on the 4th.

The rate of admission on Saturday is Re. 1 each for adults and annas 8 each for children, Students, and Soldiers and Sepoys in uniform. On Sunday a uniform rate of 4 annas each will be charged. School children below the age of 12 years will be allowed free on Sunday between 11 A.M. and 3 P.M.

Indian and European Refreshments will be sold as usual.

The Mysore Infantry Band will play on Saturday.

The public will not be admitted into the Gardens on the above days except on business connected with the Show.

Schedules of prizes, Entry Forms and any other particulars may be had from the undersigned.